

To

M/s New Technical Associates,
86-Sitara Sapna City Daewoo Road.
Faisalabad. (Mob: 0345-7721837)

No. _____/DD (P&D)/WASA/2018

Dated: _____/2018.

Subject: **REPAIR OF WASTE WATER & STORM WATER DISPOSAL ARRANGEMENT 61750 RFT NETWORK IN MADINA TOWN, ALLAMA IQBAL COLONY, PEOPLE COLONY, SAMANABAD, MILLAT TOWN, GHULAM MUHAMMAD ABAD, GULBERG AND CIVIL LINES AREAS, FAISALABAD.**

This is to notify you that your bid dated 21-02-2018 for execution of the subjected work for the Contract Price of Rs.7,18,27,905/- Seven Crore Eighteen Lac Twenty Seven Thousand Nine Hundred Five Rupees Only (as corrected and modified in accordance with the Instructions to Bidders) is hereby accepted by our Agency. The time limit for the completion of work is (100 Days) which will be reckoned from the date of issuance of this letter subject to strict financial regularities and other codal formalities.

Accepted rates are as under: -

S. No.	MRS Rates	Description	Unit	Qty	Rate (Rs.)
1	C-4/46	Dismantling and removing road pavement, etc., including screening and stacking of byproducts upto one chain lead (30 meter).	100 Cft.	22456.25	786.00
2	C-4/29	Dismantling brick or flagged flooring without concrete foundation.	100 Sft.	23962.50	500.00
3	C-4/19(b)	Dismantling cement concrete plain 1:3:6.	100 Cft.	21673.16	2500.00
4	C-3/42	Earth work excavation in open cutting for sewers and manholes as shown in drawings including shuttering and timbering, dressing to correct sections and dimensions according to templates and levels, and removing surface water, in all types of soil except shingle gravel and rock.	1000 Cft.	1043084.63	4500.00
		(i) 0 ft to 7 ft. Depth	1000 Cft.	58585.55	6000.00
		(ii) 7 ft to 15 ft. Depth			
5	C-21/1	Providing and laying R.C.C. pipe moulded with cement conc 1: 1.5: 3 with spigot or collar joint etc, including cost of reinforcement, conforming to B.S 5911 part-I 1981 class "L" including carriage of pipe from factory to site of work, lowering in trenches to correct alignment and grade, jointing, cutting pipes where necessary, finishing and testing etc. complete.			
		9" dia	P.ft.	40135	340.00
6	C-21/3	Providing and Laying R.C.C. pipe sewer moulded with cement concrete 1:1.5:3 conforming to ASTM specification C-76-79, Class-II, Wall-B, including carriage of pipe from factory to site of work, lowering			

S. No.	MRS Rates	Description	Unit	Qty	Rate (Rs.)
		in trenches to correct alignment and grade, jointing with rubber ring, cutting pipes where necessary, testing etc. complete.			
		12" dia	P.ft.	7995	390.00
		15" i/d	P.ft.	2905	500.00
		18" dia	P.ft.	3910	525.00
7	C-3/13	(i) Rehandling of earth work.			
		(a) Lead upto a single throw of Kassi, phaorah or shovel.	1000 Cft.	744392	786.00
	C-3/24a,c	(ii) Compaction of earth work.			
		(a) Mixing, moistening earth to optimum moisture content in layers for compaction etc. complete.	1000 Cft.	744392	100.00
		(iii) Ramming of earth work.	1000 Cft.	744392	100.00
8	C-21/10	Restoration of soling	100 Cft.	23962.5	2500.00
9	C-21/15A	Providing/fixing 6" thick R.C.C. manhole cover with tee shaped C-I, frame 22" I/d (frame 37.324 kg) as per standard drg. & specifications.	- P.set	607	7000.00
10	C-21/9	Extra for making and finishing benching floor work in manhole chamber with 1/8" thick cement finish.	100 Sft.	8172.90	786.00
11	C-6/5	Cement concrete plain including, placing, compacting, finishing, and curing complete (including screening and washing of stone aggregate.			
		(I) P.C.C. 1:3:6	100 Cft.	34172.39	15000.00
		(II) P.C.C. 1:2:4	100 Cft.	11355.53	21000.00
12	C-7/7	Pacca brick work other than building upto 10 ft height in 1:3 cement sand mortar.	100 Cft.	37142.45	20000.00
13	C-7/10	Extra for pacca brick work in steining of wells or any other circular masonry.	100 Cft.	37142.45	1000.00
14	C-11/8	Cement plaster "1/2 thick (1:3) cement sand mortar upto 20' height.	100 Sft.	72250.04	2000.00
15	C-6/2	Dry rammed bricks or stone ballast 1.5" to 2" gauge.	100 Cft.	12499.23	3500.00
16	C-4/46	Dismantling and removing road pavement etc, including screening and stacking of by products upto chain (30m) lead.	100 Cft.	27300.00	500.00
17	C-3/44	Excavation of trenches in all kinds of soil, except cutting rock, for water supply lines upto 5' depth from ground level, including trimming/dressing side, leveling the bed of trenches to correct grade and cutting pits for joints etc. complete in all respects.	1000 Cft	191100	4500.00
18	C-3/21	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft.			
		b.in ordinary soil.	1000 Cft	1369	6000.00

S. No.	MRS Rates	Description	Unit	Qty	Rate (Rs.)
19	C-23/23	Providing and Laying cutting, jointing, testing and disinfecting Asbestos Cement / Fiber pipe line in trenches with comet joint and rubber ring complete in all respect:- B Class Working Pressure 425 mm (16" dia)	P.Rft.	6625	2450.00
20	N.S	P/Fixing non return valve C.I body having full flow with stainless steel body seat / ring and synthetic imported rubber sheet on other side and imported stainless steel shaft pin open able type complete. 425 mm (16" dia)	Each	2	207000.00
21	N.S	Providing and fixing cast iron specials of B.S.S Class-B (such as bends, tees, crosses, collars, reducer, tail pieces, flanged socket, flanged spigot, cap, taper, angle branches, plugs etc.) for asbestos cement pipe line, with comet joints and rubber ring complete. 16" dia	P.Kg.	1085	95.00
22	C-3/13	(I) Re-handling of earthwork lead upto single throw of kassi, pharoah or shoevel.	1000 Cft	152880	786.00
	C-3/24	(II) Compaction of Earth Work (soft ordinary or hard soil).	1000 Cft	152880	100.00
		(III) Remaining of Earth Work.	1000 Cft	152880	100.00
23	C-6/3	Cement concrete brick or ballast 1 1/2" to 2" gauge in foundation and plinth Ratio (1:4:8)	100 Cft	243	12000.00
24	C-6/5	Cement concrete plain including, placing compacting finishing and curing complete (including screening and washing of stone aggregate). (1:2:4)	100 Cft	34.03	21000.00
25	C-6/1-6	P/L reinforced cement concrete (including prestressed concrete), using coarse sand and aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete. (a) (i) Reinforced cement concrete in roof slab, beams, columns, lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects:- (3) Type C (nominal mix 1:2:4)	P.Cft.	43.63	400.00
26	C-11/8	Cement plaster 1:3 up to 20' height 1/2" thick.	100 Sft	216.00	2000.00
27	C-7/7	Pacca brick work other than building upto 10 ft height (1:3) cement sand mortor.	100 Cft	357.75	20000.00
28	C-6/9	Fabrication of mild steel reinforcement of cement concrete including cutting, bending, laying in position, making joints and fastenings, including cost of binding reinforcement (also includes removal of rust form bars. b) Deformed bars	100 kg	109.07	12000.00
29	C-21/15a	Providing/fixing 6" thick R.C.C. man hole cover with tee shaped C.I frame 22" dia frame 37.324 kg. and as per standard specification.	No.	6.00	7000.00
30	N.S	P/Fixing M.S pipe 16" dia 3/8" thick including epoxy paint two coats on each external & internal surface.	P.Rft	60.00	10000.00
31	N.S	P/Fixing M.S flange 3/4" thick for 16" dia pipe including facing, holing & welding on pipe cost also included nut bolt and rubber sheet complete.	Each.	12.00	12000.00

S. No.	MRS Rates	Description	Unit	Qty	Rate (Rs.)
32	N.S	Providing and fixing butter fly valve with C-Class working pressure 425mm P.N 10	P.Sft.	2.00	115000.00
33	N.S	Providing and fixing sand (local Lahore) in trenches.	P.Cft.	46427.64	20.00
Part-B:-					
1		Providing of pit sand (New Lahore Sand), rehandling in trenches, flooding, leveling & dressing complete.	Per Cft	72823.40	20.00
2		Supplying, laying, granular material crushed stone) 1/2" to 1" gauge under pipe line and up to half diameter of pipe.	Per Cft	18429.40	55.00
3		C.I Step @ wt. 3kg each in manhole chambers l/c carriage setting the same in work to correct lines and levels.	- Each	893.00	300.00
4		Making connections of sewer line with manhole of existing sewer line including plugging of sewer line, bailing out of water, desilting, dismantling of brick wall, laying of pipe in position, filling of dismantled place with cement sand and road and concrete brick complete all respect.			
		9" dia to 12" dia	- Job	16.00	3000.00
		9" dia to 15" dia	- Job	7.00	3000.00
		12" dia to 18" dia	- Job	2.00	4000.00
		12" dia to 24" dia	- Job	1.00	6000.00
		12" dia to 24" dia	- Job	1.00	6000.00
		15" dia to 24" dia	- Job	1.00	8000.00
		18" dia to 24" dia	- Job	1.00	8000.00
5		ESMP Cost			
		1 drinking water analysis	- Job	1	1000.00
		Waste Water sample analysis	- Job	1	1000.00

We accept that Mr. Khawaja Mehboob Ellahi retired Deputy Managing Director WASA, Faisalabad be appointed as the Adjudicator.

You are hereby instructed to proceed with the execution of the said Works in accordance with the Contract documents.

TERMS & CONDITIONS: -

- All the work will be carried out strictly in accordance with PHE, B & R specification and to the entire satisfaction of the Controlling Officer, Engineer In-charge.
- Director (DC-II) WASA, Deputy Director (DC-II) WASA will be the Controlling Officer, Engineer Incharge respectively for the purpose of this work.
- You will furnish the following documents to the undersigned within (15) days from the receipt of this letter for the completion of Contract Agreement.
 - General power of Attorney or special power of Attorney and original partnership deed duly attested from the 1st class Magistrate/Oath Commissioner. In case of sole proprietor, an affidavit duly attested by the 1st class Magistrate /Oath Commissioner.
 - Detail construction schedule relating to the period of execution of work.
- This letter will be deemed as Contract Agreement till the formal agreement is signed. All other terms and conditions / general conditions shall become effective from the date of receipt of this letter.
- This letter of acceptance shall be an integral part of the contract agreement when signed.
- Please attend the office of Deputy Director-I (P&D) WASA, to complete the contract agreement within (15) days from the issuance of this letter.
- Finance Department Govt. of Punjab. Notification No. RO Tech FD,I-2/83(VI) dated: 29.03.2005, Notification No. RO Tech FD-I-2/83(VI)(P) dated: 06.04.2005 and Notification No. RO Tech FD,I-2/83(VI)(P) dated: 24.01.2006 &

Notification No. RO Tech FD,I-2/2012 dated: 04.09.2012 is applicable on this work.

8. 10% amount of each running / final bill will be withheld by Engineer Incharge, which will be released after clearance of site and on issuance of such certificate by Engineer Incharge.
9. The Additional Performance Security amounting Rs.67,00,000/- in shape of CDR No.0000200610 issued date 12/03/2018 issued by The Bank of Punjab G. M. Abad Branch Faisalabad is hereby acknowledged.
10. **Earnest Money** CDR No.0000198528 amounting Rs.18,00,000/- issued date 21-02-2018 issued by The Bank of Punjab G. M. Abad Branch Faisalabad will be released by (P&D) to the contractor after production the copy of Running Bill passed by the Audit and work security amount will be greater than the Earnest Money Amount.

1


Deputy Director-I (P&D)
Water & Sanitation Agency,
FDA, Faisalabad.

Dated: 19-03 /2018.

Endst. No. 603-612 /DD (P&D)/WASA/2018

A Copy to the: -

1. Managing Director WASA, FDA, Faisalabad.
2. Deputy Managing Director (Engineering) WASA, FDA, Faisalabad.
3. Deputy Managing Director (Services) WASA, FDA, Faisalabad.
4. Director (P&D) WASA, FDA, Faisalabad.
5. Director (Finance) WASA Faisalabad.
6. Director (DC-II) WASA, FDA, Faisalabad. (Work Executing Directorate). Copy of T.S Estimate, Drawings & Profile attached for execution of work.
- ✓ 7. Procurement Specialist City Program Unit DCO Office Faisalabad
8. Deputy Director-II (P&D) WASA, FDA, Faisalabad.
9. Deputy Director (QCD) WASA, FDA, Faisalabad.
10. Master File.


Deputy Director-I (P&D)
Water & Sanitation Agency,
FDA, Faisalabad.

